Konkan Crest Constructions

Mapusa Market Road, Bardez, Goa 403507 | Reg: CC/GOA/2019/441

Project: Proposed G+1 Residential Villa for Mr. Siddharth V. Kamat, Porvorim, North Goa
Total Quoted Amount: Rs. 54,69,241
Completion Timeline: 10 Months (excluding 15 days monsoon window)
Warranty Terms: 12 months defects liability
Payment Terms: 15% Advance on work order, 75% Stage-wise civil and finishing milestones, 10% on completion
Material Specifications: Fe 550D TMT Reinforcement Steel (Tata Tiscon), UltraTech Super Cement, M25 Concrete Mix with slump test verification, Kohler / Jaquar CP fittings, Dulux Weathershield exterior painting, Astral CPVC pipes.

Detailed Bill of Quantities (BOQ)

Item Description	Quantity	Rate	Amount
Earth excavation & foundation trenches	180 cu.m	Rs. 440	**Rs. 79,200**
Plain Cement Concrete 1:4:8 under footings	34 cu.m	Rs. 5,100	**Rs. 1,73,400**
RCC M25 grade in superstructure columns, beams and slabs	64 cu.m	Rs. 11,200	**Rs. 7,16,800**
Fe 550D Tata Tiscon TMT Bar reinforcement	6.7 MT	Rs. 73,500	**Rs. 4,92,450**
Laterite red block masonry external walls	235 sq.m	Rs. 1,800	**Rs. 4,23,000**
Two coat sand-faced plastering with waterproofer	760 sq.m	Rs. 410	**Rs. 3,11,600**
Internal plumbing & Kohler/Jaquar sanitaryware	Lump sum	-	**Rs. 6,40,000**
Electrical wiring (Polycab) with modular switches	Lump sum	-	**Rs. 5,60,000**
Vitrified tile flooring (Somany) and flush doors	210 sq.m	Rs. 1,950	**Rs. 4,09,500**
Terrace brick-bat coba waterproofing & exterior painting	Lump sum	-	**Rs. 5,63,291**