Gomes Dias Builders Pvt. Ltd.

Campal Heritage Complex, Panaji, Goa 403001 | Reg: GOA-BLD-88219

Project: Proposed G+1 Residential Villa for Mr. Siddharth V. Kamat, Porvorim, North Goa
Total Quoted Amount: Rs. 56,46,300
Completion Timeline: 11 Months from commencement
Warranty Terms: 24 months defects liability + 5 years terrace waterproofing leakage guarantee
Payment Terms: 20% Advance on signing, 70% Stage-wise progress billing (foundation, plinth, slab 1, slab 2, finishing), 10% on completion
Material Specifications: Fe 550D TMT Reinforcement Steel (Tata Tiscon / JSW Neosteel), UltraTech / ACC OPC 53 Grade Cement, M25 Ready-Mix Concrete for roof slabs, Jaquar sanitary fittings, Asian Paints Royale luxury emulsion, Finolex concealed conduits.

Detailed Bill of Quantities (BOQ)

Item Description	Quantity	Rate	Amount
Earthwork excavation & site clearance in soft/hard rock	180 cu.m	Rs. 450	**Rs. 81,000**
PCC 1:4:8 under footings and plinth beams	35 cu.m	Rs. 5,200	**Rs. 1,82,000**
RCC M25 grade in isolated footings, columns & plinth beams	65 cu.m	Rs. 11,500	**Rs. 7,47,500**
Fe 550D High yield strength ribbed steel reinforcement (Tata Tiscon)	6.8 MT	Rs. 74,000	**Rs. 5,03,200**
Laterite stone masonry in CM 1:6 for external walls (Goan red stone)	240 sq.m	Rs. 1,850	**Rs. 4,44,000**
Internal & external plastering with waterproofing compound	780 sq.m	Rs. 420	**Rs. 3,27,600**
Plumbing, CPVC piping (Astral) & sanitary installation (Jaquar)	Lump sum	-	**Rs. 6,85,000**
Electrical wiring (Finolex/Polycab) with modular switches (Legrand)	Lump sum	-	**Rs. 5,90,000**
Vitrified tile flooring 800x800mm (Kajaria) & teakwood doors	210 sq.m	Rs. 2,100	**Rs. 4,41,000**
Terrace elastomeric waterproofing & 3-coat exterior painting (Asian Paints)	Lump sum	-	**Rs. 6,45,000**