VAZ PATIL CONSTRUCTIONS LLP

Margao Commercial Center, South Goa 403601 | LLPIN: AAA-9182

Project: Proposed G+1 Residential Villa for Mr. Siddharth V. Kamat, Porvorim, North Goa
Total Quoted Amount: Rs. 51,72,318
Completion Timeline: 9 Months from commencement
Warranty Terms: 12 months defects liability for workmanship
Payment Terms: 25% Advance booking deposit, 65% Stage-wise milestone billing, 10% on completion handover
Material Specifications: Fe 500D TMT Reinforcement Steel (JSW / Kamdhenu), ACC / Ambuja OPC 43 Grade Cement, M20 Grade site-mixed concrete, Cera sanitaryware, Berger Weathercoat exterior paint, Supreme PVC drainage pipes.

Detailed Bill of Quantities (BOQ)

Item Description	Quantity	Rate	Amount
Site preparation, excavation and backfilling	175 cu.m	Rs. 420	**Rs. 73,500**
PCC 1:4:8 base course foundation	32 cu.m	Rs. 4,900	**Rs. 1,56,800**
RCC M20 framework columns, beams and roof slabs	62 cu.m	Rs. 10,800	**Rs. 6,69,600**
Fe 500D TMT Rebar (JSW Steel)	6.5 MT	Rs. 71,000	**Rs. 4,61,500**
Concrete solid block masonry 150mm thick	230 sq.m	Rs. 1,650	**Rs. 3,79,500**
Cement sand plaster smooth finish	750 sq.m	Rs. 380	**Rs. 2,85,000**
Plumbing, water supply and drainage works (Cera fixtures)	Lump sum	-	**Rs. 5,80,000**
Concealed electrical installation & distribution panel	Lump sum	-	**Rs. 5,20,000**
Ceramic flooring and bathroom wall tiling	205 sq.m	Rs. 1,750	**Rs. 3,58,750**
Waterproofing of wet areas and exterior painting (Berger)	Lump sum	-	**Rs. 4,87,668**